BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41629

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work:Desilting and footpath improvements in various roads of Tatanagara and surrounding areas inw ard no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRIKANTH K S (AAKAR CONSTRUCTION)	
				In Figures	In Words
1	1723.68	Removing and refixing stone slabs of drains and pointing in CM 1:3 (Page No. 27, Item No. 5.33, PWDSR 2018-19)	Sqm	86.0	Rupees Eighty Six Only
2	532	KSRRB 300-2 : Earth work excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 (Page No. 143, Item No. 19.1, PWDSR 2018-19)	Cum	106.0	Rupees One Hundred Six Only
3	191.52	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. - 100 mm thick (Approved data rate enclosed)	Sqm	1630.0	Rupees One Thousand Six Hundred Thirty Only
4	452.2	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum	67.0	Rupees Sixty Seven Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

15/06